

- RF absorption & cooling by water
- Excellent peak & average power capability
- High reliability & long life-time
- Free of maintenance & wear parts
- RoHS compliant
- Designed for X-band LINAC applications

Parameter		Value			
Footprint Drawing No.		FP-10074172			
Product Type		RF Load			
Configuration		Water Load			
Center Frequency fo		9300 MHz			
Bandwidth BW		± 10 MHz			
Input Power		Options:	Xp = 1	Xp = 2	
	Input Peak Power		2 MW	2.5 MW	
	Input Average Power		2 kW	2.5 kW	
Return Loss		≥ 30 dB			
VSWR		< 1.065			
RF Waveguide		WR112			
RF Flanges / Connectors		WR112 cover flange, UG-51/U, with 4x 8-32 UNC-28 threads			
Cooling System		demineralized water			
Water Tube Materials		Stainless steel			
Wa	ter Connectors	2x 1/4" hose barb fittings, stainless steel			
Water Inlet Temperature (nominal)		selectable between 20°C and 40°C			
Water Inlet Temperature Range		± 2°C			
Water Flow Rate		≥ 300 l/h			
Water Pressure Drop		< 2 bar @ minimum flow rate			
Water Inlet Pressure		≤ 10 bar			
Water Leak Test Pressure		15 bar for 10min			



Data Sheet LW-WR112-01-9300-Xp-Xw

Water Load 9300MHz WR112

Waveguide Dielectric Filling Gas	SF6		
Gas Pressure	nominal:	3 bar absolute	
	maximum :	4 bar absolute	
Gas Leak Rate (Helium)	< 5·10 <sup>-4</sup> mbar l/s		
	tested with Helium pressurization at 2.5 bar gauge		
Ambient Temperature	operating :	10°C to 40°C	
	storage :	0°C to 60°C	
Relative Humidity	< 80%, non-condensing		
Dimensions	see footprint drawing		
Weight	0.7 kg approximately		
Mounting Orientation	any		

## **Ordering Code**

## LW-WR112-01 - Xp - Xw

Variable	Description	Value Options	
Хр	Input Power Option	1 (2MW / 2kW)	<b>2</b> (2.5MW / 2.5kW)
Xw	Water Inlet Temp. [°C]	2040	

## Notes:

- 1 <u>Water</u> quality, temperature, flow, and input pressure need to be controlled carefully according to the specified values. Air bubbles in the cooling channel have to be avoided. The device does not include any sensorics and interlocks for water temperature, flow or pressure.
- 2 <u>Low-Power Acceptance Tests</u>: The following tests will be performed at the AFT factory before shipment: (1) small-signal network analyzer measurements of input return loss vs. frequency at room temperature, (2) water leak test, and (3) He-gas leak rate testing.
- 3 <u>Documentation</u>: An owner's manual is supplied for providing information on the installation, operation and maintenance of the device. The documentation will also include specification, footprint drawing.

As an *option to be ordered separately*, extended documentation is available in terms of a low-power RF test report (viewgraphs S-parameters vs. frequency) or written factory test protocol.

Rev.	Remark	Date	Name
0	Initial	23.06.2017	C. Weil
	Footprint drawing no.	27.04.2018	C. Weil